

- Mangawhai Community Park Site Boundary
- New 3 meter wide Shared Path
- Secondary Pathway
 - Wetland / Stream

Boardwalk / Benched Track


Main Pedestrian & Vehicle Entrance

Secondary Pedestrian & Vehicle Entrance

Potential pedestrian refuge to improve safety of pedestrians accessing the Reserve - Locations to be coordinated and approved by NTA Road Safety & Traffic Engineering

Existing pedestrian refuge

(9) Key note number



KEY Note

- Existing entrance to Museum and Historic Village. Include (1)new dedicated pedestrian access paths and pedestrian refuge. Reduce the width of the vehicle entrance to slow traffic and increase pedestrian space and landscaping opportunities.
- (2) Secondary vehicle access to be widened to allow access and circulation for service vehicles, Art Centre vehicles and buses.
- (3) Mangawhai Community Park entrance statement. Signage, lighting, landscaping and space for temporary, seasonal / event installations.
- Mangawhai Museum, Historical Village and formalised existing (4) car park. Additional space and paths are accommodated for safe and comfortable pedestrian access and movement.
- Proposed bus maneuvering and parking space. Vehicle tracking (5) and design required to ensure sufficient maneuvering space.
- 6 Potential bus turn around and visitor drop off zone located between the museum and proposed new arts building.
- New arts building and shared outdoor / plaza space. (7)
- 8) New two pan public toilet.
- 9 Existing Norfolk Pines retained where possible and supplemented with a native specimens.


- New bridge across the existing overland flow path and wetland (10) to allow for new shared path alignment and stormwater flow to the wetlands.
- Existing stormwater outlet to be extended to allow for new (11)shared path alignment. NOTE the shared path enters Road Reserve in this area.
- This section of the shared path needs to traverse a level (12)change of approximately 5 meters. To gain an all abilities path gradient a boardwalk or benched / retained path of approximately 70 meters will be required.
- (13) A new pedestrian access to the Park and connection to the shared path. Access supported by a new pedestrian refuge.
- Existing BMX Pump Track. This section of shared path may (14) require a section of low boardwalk or drainage to allow for draining of flood waters.
- Open passive recreational space, sports training and events (15)area. Potential overflow parking for MAZ events.
- Existing Skate Park, recently extended and upgraded. (16)
- Potential location for proposed MAZ Clubrooms, overlooking (17)the activity zone. This location needs further investigation, including investigation into required associated car parking, building size. Geotechnical assessment and survey required to ascertain if conditions are suitable. NOTE required services to be considered.







Mangawhai Community Park Concept Plan L106 - Landscape Concept Plan Sheet 1 of 2 Rev 06,10.09.20 Discussion Document STELLAR



(26) New Pump Track.

- New open green space adjacent to the pump track with shade (27) trees and picnic facilities.
- (28) Storm water outlet from the Fire Station. Create a planted swale to direct storm water to wetland or soakage area. Potential for interpretive / educational signage around SW treatment / management.

Mangawhai Community Park Concept Plan L107 - Landscape Concept Plan Sheet 2 of 2 Rev 06, 10.09.20 Drawn:AN **Discussion Document STELLAR**



